Update on the AGS CNI Polarimeter

- Overview of CNI polarimeter
 - Kinematics
 - Set up
 - Features
- AGS noise study update
- Schedule for installation and operation

Jeff Wood, UCLA for the AGS Polarimeter Group

RHIC Spin Layout



Kinematics of pC CNI Polarimeter

pC elastic scattering in the Coulomb-Nuclear Interference (CNI) region

- $A_N \propto Im(\phi_{non-flip}^h \times \phi_{flip}^{em*})$
- Measure recoil Carbons at ~90 deg.
- Calculate left-right asymmetry
- Kinematic range:
 - $0.003 < -t (GeV/c)^2 < 0.03$
 - $0.1 < T_{\text{recoil C}} (\text{MeV}) < 1.1$
 - 60 < tof(ns) < 170



Experimental Setup



- thin carbon target is moved into the beam for measurements
- AGS target width: 600 µm

RHIC: 5 µm

AGS Performance in 02

Red line: Simulation with 2002 running conditions, 70% as input from LINAC. Emittance taken as measured.

 $v_x = 8.70$, $v_y = 8.80$ for most resonance except 36+ v_y with $v_x = 8.68$, $v_y = 8.90$ and ac dipole not fired.

Blue line: Simulation with fast ramp rate and more tune separation at $36+v_y$ and good betatron tunes for $48-v_y$.



New polarimeter is expected to help avoid polarization losses

RSC meeting 9/16/02

New AGS CNI Polarimeter will help

- Fast feedback for machine tuning
 - No dead time
 - $\sim 1M$ events/s (with 6 bunches in AGS)
- Ability to measure during the ramp
 - Can measure 2 ms bins with several ramps
- Detector acceptance throughout AGS momentum range (2.27 < p_{beam} (GeV/c) < 24.32)



Acceptance: $90^{\circ} \pm 2.7^{\circ}$ Worst case recoil angle: $\theta_{recoil} = 88^{\circ}$ (at p=2.27, -t=0.03)

RSC meeting 9/16/02

Update on AGS Noise Study

- Reflection signal from passing bunches seen in RHIC and AGS
- Pulsed wire tests
 - Current pulse sent through chamber
 - Signal induced on detector



Shielding Box

Addition of shield box reduces signal size





- Effect on measurement is minor
 - signal persists for ~60 ns

8

Noise Subtraction



- Build a new module based on experience from E950
 - Or
- Use WFD if possible

Noise difference between left and right may cause problems

Installation Schedule

First beam in AGS scheduled for 10/15

- Installation of chamber must be complete
 - Chamber itself motor tests complete 9/15
 - Detectors ready
 - Preamps arriving end of Sept.
 - Cables pulled first week in Oct.
 - Targets delivered from IUCF by end of Sept.

Commission/Operation Schedule

- Set up DAQ
 - New WFD modules arrive mid-Nov.
 - Program WFDs Nov./Dec.
 - Shapers, Bias Volt. Supply, etc. in hand
- May try dC scattering during RHIC commissioning in Dec.
- First pol. p in AGS Jan.

Summary

• AGS CNI pol. will provide fast feedback for machine tuning

– Minimize polarization loss

- Noise studies look promising
- Installation by 10/15
- Polarized p beam in Jan.